

Project Details

Philadelphia, PA

July, 2005

Application: Hospital Facility Central Plant Package System

Description

VariPrime™ chilled water package with 900 total tons completely fabricated inside a factory provided enclosure

Technical Data

- (2) 450 Ton Centrifugal Chillers
- (3) Primary Chilled Water Pumps
 - 750 GPM at 100' TDH
 - 30 HP
- (3) Condenser Water Pumps
 - 1350 GPM at 50' TDH
 - 25 HP
- 4160 Volt Electrical Service
- (3) VFD's for Condenser Pump Speed Control
- (3) VFD's for Primary Pump Speed Control





 **Resylution™**
A Division of Systecon Inc.